

Novo Resources Corp. Beatons Creek Fresh Feasibility Study Update

14.06.2022 | [GlobeNewswire](#)

HIGHLIGHTS

- A feasibility study for mining of the Beatons Creek gold project ("Beatons Creek") Fresh mineral resource ("Feasibility Study") is underway, with completion targeted by mid-Q4 2022

- Metallurgical and geotechnical diamond drilling programs have been completed, with assaying and metallurgical test work underway and due for completion by the end of July 2022

- Phase one of a mineral resource definition reverse circulation ("RC") drilling program will be completed by the end of June 2022. Results received to May 31, 2022 include significant, high-grade intercepts (> 40 gram-metres gold) of:

- 3.5 m at 43.62 g/t gold from 47 m in GHF0526
- 5.5 m at 16.02 g/t gold from 30 m in GHF0269
- 1.5 m at 48.84 g/t gold from 42.5 m in GHF0500
- 4.5 m at 15.23 g/t gold from 47.5 m in GHF0523
- 2 m at 28.14 g/t gold from 75.5 m in GHF0200
- 3 m at 18.5 g/t gold from 72.5 m in GHF0181
- 3 m at 17.85 g/t gold from 39 m in GHF0014
- 1.5 m at 31.29 g/t gold from 43.5 m in GHF0498
- 2.5 m at 17.66 g/t gold from 41.5 m in GHF0490
- 2.5 m at 16.16 g/t gold from 82 m in GHF0216
- 3 m at 15.3 g/t gold from 61.5 m in GHF0554

- Mineral resource definition drilling to date has confirmed the high-grade nature, strong continuity, and thickness of the Fresh mineralized material

- Commencement of Phase Two mining of the Beatons Creek Fresh deposit is subject to receipt of approvals from various Western Australian regulatory departments¹.

VANCOUVER, June 14, 2022 - [Novo Resources Corp.](#) ("Novo" or the "Company") (TSX: NVO, NVO.WT & NVO.WT.A) (OTCQX: NSRPF) is pleased to provide an update on the Feasibility Study and key initial results from the ongoing resource definition drilling program.

"The Fresh component of Beatons Creek accounts for approximately 65% of the global Beatons Creek mineral resource estimate and is integral to Novo's operational success. With mining of the Oxide mineral resource nearing completion^{1,2}, we have shifted our focus on the ground to complete key exploration and development activities for Phase Two Fresh operations at Beatons Creek. Importantly, our resource definition drill program has already delivered excellent, near-surface results which confirm the high-grade nature of the Fresh mineral resource and supports Novo's plans to accelerate the Feasibility Study, while working with Western Australian regulatory departments to obtain requisite approvals," commented Mr. Michael Spreadborough, Executive Co-Chairman, acting Chief Executive Officer and a director of Novo.

BEATONS CREEK STATUS

Operations will be paused at Beatons Creek, with a controlled and phased wind-down of operational activities through Q3 2022, as outlined in the Company's news release dated June 14, 2022¹.

Commencement of Phase Two mining of the Fresh mineral resource at Beatons Creek, is subject to receipt of approvals from various Western Australian regulatory departments and the successful completion of the Feasibility Study, including a final investment decision by Novo's board of directors¹.

BEATONS CREEK RESOURCE DEFINITION DRILLING

Building upon recent knowledge gained during mining activities completed at the Grant's Hill deposit, which forms part of Beatons Creek, Novo has been undertaking 20 m by 20 m resource definition RC drilling across

key areas at Grant's Hill, which contains the majority of the known Fresh mineralization³.

This drill program commenced at the end of October 2021, with the Company accelerating drilling in January 2022 through three RC drill rigs. At the end of May 2022, approximately 31,700 m (397 holes), with an average depth of 80 m per hole, were drilled into the Grant's Hill project area.

Drilling at Grant's Hill has been systemically trending in a north-westerly direction from the Oxide open pit boundary, testing the extent of the known mineralization ('lodes') identified in the previously released mineral resource estimate³. Whilst the natural topography and landscape has presented some challenges, the drill coverage was designed to test as many lodes as possible (Figures 1 & 2 below). To date, drilling programs have achieved good spatial coverage reaching up to 400 m in width and 600 m in length. These drill programs have been targeting known lodes including the M0, M1, M2 and M3, with the primary focus targeting the well-endowed M1 and M2 lodes.

<https://www.globenewswire.com/NewsRoom/AttachmentNg/e3717933-4cef-4c3c-a735-56506d81764a>
(Figure 1: Grant's Hill Fresh mineral resource definition RC drilling)

To gain further confidence in the lodes, a 30,400 sq m area was drilled at a 10 m by 10 m spacing immediately adjacent to the recently mined Grant's Hill pit. This drilling comprised 73 holes for 5,080 m drilled, in addition to the already drilled 20 m by 20 m pattern (Figure 2 below).

Figures 3, 4 and 5 illustrate the lodes intersected by recent resource definition drilling, along with drilling results received to date. Results are encouraging, indicating that the principal M1 and M2 lodes remain open and continuous along plunge. These results also confirm the thickness and tenor of the mineralization intercepted in prior drilling programs. Refer to Table 1 for a list of all significant intervals greater than 0.5 g/t gold.

BEATONS CREEK RESOURCE EXTENSION DRILLING

Significance of the resource definition results allows Novo to plan for the next phases of drilling, extending drill coverage in a north-westerly direction with an expectation to grow the current mineral resource estimate³ ("MRE") (Figure 2 below shows priority 1 to priority 4 phases). The next stage of resource extension drilling will be targeting areas of existing sparse drilling information and planned drilling aims to increase resource confidence, through the upgrade of current inferred mineral resources³ and unclassified mineralization. The resource extension drilling program will be completed in a staged approach, targeting higher-priority areas in the first instance and progressing to lower priority areas to potentially grow the inferred mineral resource³ and inform further studies and life-of-mine planning.

The drilling program will continue for the remainder of CY2022 and into H1 2023 and is expected to define the updated extent of the Beatons Creek Fresh mineral resource.

<https://www.globenewswire.com/NewsRoom/AttachmentNg/5a7d935f-859b-4ff8-97f4-b3ed6c33c78a>
(Figure 2: Plan view of Beatons Creek Fresh mineral resource definition and extension programs)

<https://www.globenewswire.com/NewsRoom/AttachmentNg/25076229-f329-4cf8-a438-01c89f2556e2>
(Figure 3: Section view A-A' Beatons Creek Fresh mineral resource definition and extension programs)

<https://www.globenewswire.com/NewsRoom/AttachmentNg/357b2b53-6d7e-4ee8-8056-841777933a61>
(Figure 4: Section view B-B' Beatons Creek Fresh mineral resource definition and extension programs)

<https://www.globenewswire.com/NewsRoom/AttachmentNg/41ffd4cb-c8dd-43d9-b8a8-acb43f5a2207>
(Figure 5: Section view C-C' Beatons Creek Fresh mineral resource definition and extension programs)

BEATONS CREEK FRESH FEASIBILITY STUDY

The results from the resource definition and extension drilling program will inform an update to the MRE for Beatons Creek, with the upgraded MRE providing the foundation for the Feasibility Study.

Data collection and analysis programs are underway to better define parameters for:

- Metallurgical recoveries and an optimization of the Golden Eagle processing facility ("Golden Eagle Plant")
- Geotechnical, hydrogeological and hydrological conditions to be encountered in the open pits
- Geochemical properties of the various materials being mined to ensure they are appropriately managed

during and post-mining operations at Beatons Creek

Other key studies which have also commenced, include:

- Updated Beatons Creek mine and waste dump designs incorporating management of any potential for acid mine drainage and mine closure commitments
- Improved understanding of the metallurgical performance of the Beatons Creek Fresh mineralized material through the Golden Eagle Plant and optimum throughput rates, as previously reported⁴
- Definition of an economic provision for additional tailings storage capacity to accommodate processing of Beatons Creek Fresh mineralized material
- Determining the suitability of current Beatons Creek infrastructure required to support mining and processing of the Fresh mineralized material, including consideration of renewable energy options for power generation and/or supply
- Mining and processing schedules
- Capital and operating cost estimates and life-of-mine cash flow forecasts
- Development of an economic mine plan and the reporting of a mineral reserve estimate in a National Instrument 43-101 Standards of Disclosure for Mineral Projects ("NI 43-101") compliant technical report

SAMPLE PREPARATION, ASSAYING AND QUALITY ASSURANCE/QUALITY CONTROL

The widths of intercepts reported are approximate true width given vertical RC holes and relatively flat lying lodes. All samples are collected as 0.5 m RC composites. Samples are split in half (c. 8 kg) at the rig and one half selected at random and submitted to the Beatons Creek on-site Intertek laboratory. Samples are dried for 24 hours. They are then fed through a Smart Crusher, where they are reduced to P90 -3 mm and 2.5 kg split off for assay. The 2.5 kg sub-sample is placed into five PhotonAssay™ pots. The pots are shipped to the Intertek laboratory in Perth where they are assayed in total by PhotonAssay™.

PhotonAssay™ is a non-destructive method, based on technology that measures gold concentration via X-ray excitation to produce gamma rays. Intertek PhotonAssay™ is NATA accredited (3244) via ISO/IEC 17025 (2017) for method PA W0002. Drill program design, quality assurance/quality control and interpretation of results is performed by qualified persons employing quality control ("QC") analysis consistent with industry best practices. PhotonAssay™ certified CRMs and blanks are included at a rate of 1 in 25 samples for QC purposes by the Company. Intertek undertakes its own QC, the results of which are provided to Novo. Approximately 2% of PhotonAssay™ samples are umpire assayed by screen fire assay. Novo does not know of any factors of drilling or sampling that could materially affect the accuracy or reliability of the assay data disclosed.

All data was verified without limitation by a qualified person by reviewing analytical procedures undertaken.

QP STATEMENT

Dr. Simon Dominy FAusIMM (CP) FAIG (RPGeo) is the qualified person, as defined under NI 43-101, responsible for, and having reviewed and approved, the technical information contained in this news release. Dr. Dominy is a Technical Advisor to Novo.

CAUTIONARY STATEMENT

The decision by the Company to produce at Beatons Creek was not based on a feasibility study of mineral reserves demonstrating economic and technical viability and, as a result, there is an increased uncertainty of achieving any particular level of recovery of minerals or the cost of such recovery, including increased risks associated with developing a commercially mineable deposit. Production has not achieved forecast to date. Historically, such projects have a much higher risk of economic and technical failure. There is no guarantee that anticipated production costs will be achieved. Failure to achieve the anticipated production costs would have a material adverse impact on the Company's cash flow and future profitability.

The Company cautions that its declaration of commercial production effective October 1, 2021 only indicates that Beatons Creek was operating at anticipated and sustainable levels and it does not indicate that

economic results will be realized.

ABOUT NOVO

Novo operates its flagship Beatons Creek gold project while exploring and developing its prospective land package covering approximately 11,000 square kilometres in the Pilbara region of Western Australia. In addition to the Company's primary focus, Novo seeks to leverage its internal geological expertise to deliver value-accretive opportunities to its shareholders.

Shareholders and Canadian media are to contact Leo Karabelas at (416) 543-3120 or e-mail leo@novoresources.com.

Australian media are to contact Cameron Gilenko (Citadel-MAGNUS) at 0466 984 953.

On Behalf of the Board of Directors, Novo Resources Corp.

"Michael Spreadborough"
Michael Spreadborough, Executive Co-Chairman and Acting CEO

Forward-looking information

Some statements in this news release contain forward-looking information (within the meaning of Canadian securities legislation) including, without limitation, that the Feasibility Study will be completed in mid-Q4 2022, that assaying and metallurgical testwork will be completed in Q3 2022, that mineral resource definition and extension drilling programs will further expand the Beatons Creek Fresh mineral resource and will continue for the remainder of CY2022 and H1 2023, and that extending drill coverage in a north-westerly direction will potentially grow the mineral resource. These statements address future events and conditions and, as such, involve known and unknown risks, uncertainties and other factors which may cause the actual results, performance or achievements to be materially different from any future results, performance or achievements expressed or implied by the statements. Such factors include, without limitation, customary risks of the resource industry and the risk factors identified in Novo's management's discussion and analysis for the three-month period ended March 31, 2022, which is available under Novo's profile on SEDAR at www.sedar.com. Forward-looking statements speak only as of the date those statements are made. Except as required by applicable law, Novo assumes no obligation to update or to publicly announce the results of any change to any forward-looking statement contained or incorporated by reference herein to reflect actual results, future events or developments, changes in assumptions or changes in other factors affecting the forward-looking statements. If Novo updates any forward-looking statement(s), no inference should be drawn that the Company will make additional updates with respect to those or other forward-looking statements.

Table 1: Significant intercepts for all drilling during the Fresh mining stage. The table is generated by calculating the average grade for each drill hole intersection constrained by the modelled M1 and M2 lodes, and a 0.5 g/t gold intersection grade cut-off for reporting. All holes are drilled on tenement M46/11 and with co-ordinates related to reference system GDA94, Zone 51.

Hole ID	Type	Depth (m)	Date Completed	Easting	Northing	Height (m)	Azimuth	Dip	Lode	From
GHF0001	RC	75	2/11/2021	199831.818	7577899.339	411.318	0	-90	M1	34.5 38.5 4 2.79
GHF0001	RC	75	2/11/2021	199831.818	7577899.339	411.318	0	-90	M2	51.5 54.5 3 2.90
GHF0004	RC	100	17/02/2022	199605.876	7577672.975	428.432	340	-89	M2	73 73.5 0.5 0.59
GHF0005	RC	96	17/02/2022	199619.976	7577658.862	426.573	10	-89	M2	68.5 70.5 2 0.69
GHF0006	RC	85	17/02/2022	199634.086	7577673.006	425.518	103	-89	M1	48 50.5 2.5 2.05
GHF0006	RC	85	17/02/2022	199634.086	7577673.006	425.518	103	-89	M2	67.5 68 0.5 1.98
GHF0007	RC	83	29/11/2021	199648.304	7577687.212	423.5	0	-90	M1	48 49.5 1.5 7.20
GHF0007	RC	83	29/11/2021	199648.304	7577687.212	423.5	0	-90	M2	65.5 68.5 3 0.88
GHF0008	RC	75	2/11/2021	199834.235	7577870.496	415.48	0	-90	M1	37.5 40 2.5 2.30
GHF0008	RC	75	2/11/2021	199834.235	7577870.496	415.48	0	-90	M2	53 56.5 3.5 1.58
GHF0009	RC	82	25/10/2021	199874.059	7577913.127	416.472	0	-90	M1	39 40 1 8.34
GHF0009	RC	82	25/10/2021	199874.059	7577913.127	416.472	0	-90	M2	55.5 58 2.5 4.95

GHF0010 RC 12 7/12/2021 199648.524 7577659.566 423.631 0 -90 M1 45.5 47 1.5 7.45
GHF0010 RC 12 7/12/2021 199648.524 7577659.566 423.631 0 -90 M2 63.5 67 3.5 0.84
GHF0011 RC 83 22/02/2022 199662.37 7577673.006 424.952 156 -90 M1 46.5 47.5 1 1.40
GHF0011 RC 83 22/02/2022 199662.37 7577673.006 424.952 156 -90 M2 64 65.5 1.5 1.08
GHF0013 RC 79 3/11/2021 199832.909 7577842.677 420.816 0 -90 M1 43 44.5 1.5 3.44
GHF0013 RC 79 3/11/2021 199832.909 7577842.677 420.816 0 -90 M2 57 60 3 1.81
GHF0014 RC 24 3/11/2021 199846.179 7577856.83 418.181 0 -90 M1 39 42 3 17.85
GHF0014 RC 24 3/11/2021 199846.179 7577856.83 418.181 0 -90 M2 54 58 4 1.39
GHF0016 RC 76 21/10/2021 199903.224 7577912.62 421.856 0 -90 M1 42.5 46.5 4 5.04
GHF0016 RC 76 21/10/2021 199903.224 7577912.62 421.856 0 -90 M2 61 62.5 1.5 2.12
GHF0018 RC 82 1/01/2022 199690.472 7577673.643 425.178 0 -90 M1 50.5 51.5 1 4.37
GHF0018 RC 82 1/01/2022 199690.472 7577673.643 425.178 0 -90 M2 64.5 65.5 1 1.20
GHF0019 RC 84 31/12/2021 199704.737 7577687.117 425.253 0 -90 M1 50.5 52.5 2 2.09
GHF0019 RC 84 31/12/2021 199704.737 7577687.117 425.253 0 -90 M2 63.5 64.5 1 1.98
GHF0020 RC 85 11/12/2021 199718.878 7577701.501 423.976 0 -90 M1 48.5 50 1.5 1.89
GHF0020 RC 85 11/12/2021 199718.878 7577701.501 423.976 0 -90 M2 60 63 3 1.60
GHF0022 RC 18 7/11/2021 199775.58 7577758.737 422.973 0 -90 M1 44 45.5 1.5 1.77
GHF0022 RC 18 7/11/2021 199775.58 7577758.737 422.973 0 -90 M2 57.5 59.5 2 1.13
GHF0023 RC 54 4/11/2021 199818.856 7577800.758 424.874 0 -90 M1 47 50 3 1.31
GHF0023 RC 54 4/11/2021 199818.856 7577800.758 424.874 0 -90 M2 58 60 2 4.54
GHF0024 RC 80 1/11/2021 199845.978 7577828.274 425.285 0 -90 M1 46 46.5 0.5 4.69
GHF0024 RC 80 1/11/2021 199845.978 7577828.274 425.285 0 -90 M2 60 62.5 2.5 1.11
GHF0025 RC 30 26/10/2021 199889.194 7577870.52 421.953 0 -90 M1 41 42 1 6.46
GHF0025 RC 30 26/10/2021 199889.194 7577870.52 421.953 0 -90 M2 55.5 60 4.5 8.15
GHF0026 RC 76 23/10/2021 199916.766 7577898.835 424.244 0 -90 M1 43.5 46.5 3 10.72
GHF0026 RC 76 23/10/2021 199916.766 7577898.835 424.244 0 -90 M2 60.5 64 3.5 2.31
GHF0027 RC 80 30/12/2021 199718.95 7577673.061 424.584 0 -90 M1 47.5 48.5 1 3.25
GHF0027 RC 80 30/12/2021 199718.95 7577673.061 424.584 0 -90 M2 60 61.5 1.5 0.95
GHF0028 RC 85 30/12/2021 199732.866 7577686.74 427.848 0 -90 M1 50 52 2 2.78
GHF0028 RC 85 30/12/2021 199732.866 7577686.74 427.848 0 -90 M2 62.5 64 1.5 2.05
GHF0029 RC 54 18/12/2021 199746.827 7577701.694 429.56 0 -90 M1 48.5 49 0.5 8.14
GHF0029 RC 54 18/12/2021 199746.827 7577701.694 429.56 0 -90 M2 62.5 64.5 2 3.45
GHF0030 RC 78 16/12/2021 199761.717 7577714.566 430.74 0 -90 M1 49.5 51 1.5 1.16
GHF0030 RC 78 16/12/2021 199761.717 7577714.566 430.74 0 -90 M2 63 67 4 1.41
GHF0031 RC 90 22/02/2022 199775.507 7577729.576 431.131 10 -90 M1 49.5 50 0.5 2.21
GHF0031 RC 90 22/02/2022 199775.507 7577729.576 431.131 10 -90 M2 61.5 64 2.5 0.71
GHF0032 RC 36 8/11/2021 199789.901 7577743.895 429.9 0 -90 M1 49 50.5 1.5 3.24
GHF0032 RC 36 8/11/2021 199789.901 7577743.895 429.9 0 -90 M2 62 63 1 2.61
GHF0033 RC 82 1/12/2021 199803.67 7577758.246 427.926 0 -90 M1 48 48.5 0.5 3.26
GHF0033 RC 82 1/12/2021 199803.67 7577758.246 427.926 0 -90 M2 60 62.5 2.5 7.74
GHF0034 RC 82 7/11/2021 199818.382 7577771.889 428.548 0 -90 M1 47.5 49 1.5 3.12
GHF0034 RC 82 7/11/2021 199818.382 7577771.889 428.548 0 -90 M2 60.5 63 2.5 2.33
GHF0035 RC 54 5/11/2021 199832.947 7577786.135 428.163 0 -90 M1 47.5 50 2.5 4.82
GHF0035 RC 54 5/11/2021 199832.947 7577786.135 428.163 0 -90 M2 61.5 63 1.5 0.75
GHF0036 RC 81 1/12/2021 199846.002 7577800.528 428.26 0 -90 M1 46.5 50 3.5 6.05
GHF0036 RC 81 1/12/2021 199846.002 7577800.528 428.26 0 -90 M2 58.5 61.5 3 7.99
GHF0037 RC 54 31/10/2021 199860.413 7577814.588 427.331 0 -90 M1 43.5 46.5 3 0.76
GHF0037 RC 54 31/10/2021 199860.413 7577814.588 427.331 0 -90 M2 58 60.5 2.5 2.53
GHF0038 RC 75 31/10/2021 199875.307 7577827.318 424.834 0 -90 M1 41 42 1 2.58
GHF0038 RC 75 31/10/2021 199875.307 7577827.318 424.834 0 -90 M2 54.5 59 4.5 1.44
GHF0039 RC 74 31/10/2021 199888.976 7577842.608 424.71 0 -90 M1 41 43.5 2.5 3.40
GHF0039 RC 74 31/10/2021 199888.976 7577842.608 424.71 0 -90 M2 57 58.5 1.5 0.61
GHF0040 RC 64 24/10/2021 199903.262 7577857.409 426.187 0 -90 M1 42.5 45 2.5 3.80
GHF0040 RC 64 24/10/2021 199903.262 7577857.409 426.187 0 -90 M2 57.5 63 5.5 4.96
GHF0042 RC 77 24/10/2021 199916.856 7577871.087 427.13 0 -90 M1 44.5 45.5 1 10.25
GHF0042 RC 77 24/10/2021 199916.856 7577871.087 427.13 0 -90 M2 60.5 64 3.5 1.60
GHF0043 RC 72 11/12/2021 199930.717 7577885.154 425.303 0 -90 M1 43 44 1 16.60
GHF0043 RC 72 11/12/2021 199930.717 7577885.154 425.303 0 -90 M2 59.5 61 1.5 7.43
GHF0044 RC 92 12/12/2021 199945.059 7577899.294 422.095 0 -90 M1 40.5 43.5 3 9.67
GHF0044 RC 92 12/12/2021 199945.059 7577899.294 422.095 0 -90 M2 55 56 1 1.04
GHF0045 RC 82 20/12/2021 199761.083 7577687.055 428.357 0 -90 M2 59 61.5 2.5 1.63
GHF0046 RC 83 19/12/2021 199775.483 7577701.002 428.925 0 -90 M1 48.5 50 1.5 2.13
GHF0046 RC 83 19/12/2021 199775.483 7577701.002 428.925 0 -90 M2 59 62 3 0.85
GHF0047 RC 83 18/12/2021 199789.734 7577715.558 429.172 0 -90 M1 45.5 46 0.5 1.26
GHF0047 RC 83 18/12/2021 199789.734 7577715.558 429.172 0 -90 M2 58.5 60.5 2 1.70
GHF0048 RC 82 17/12/2021 199803.822 7577730.03 430.27 0 -90 M1 46 47 1 2.72
GHF0048 RC 82 17/12/2021 199803.822 7577730.03 430.27 0 -90 M2 59.5 61 1.5 0.82

GHF0049 RC 81 7/11/2021 199817.509 7577743.309 429.826 0 -90 M1 45.5 46 0.5 0.60
GHF0049 RC 81 7/11/2021 199817.509 7577743.309 429.826 0 -90 M2 57.5 60 2.5 2.61
GHF0050 RC 80 1/12/2021 199832.075 7577757.86 428.284 0 -90 M1 46 47 1 0.71
GHF0050 RC 80 1/12/2021 199832.075 7577757.86 428.284 0 -90 M2 57 59 2 0.95
GHF0052 RC 76 22/02/2022 199874.501 7577800.287 425.689 94 -89 M1 40 41 1 24.17
GHF0052 RC 76 22/02/2022 199874.501 7577800.287 425.689 94 -89 M2 50.5 56 5.5 3.36
GHF0053 RC 54 7/01/2022 199888.644 7577814.429 424.792 0 -90 M1 37.5 40.5 3 2.21
GHF0053 RC 54 7/01/2022 199888.644 7577814.429 424.792 0 -90 M2 53.5 57 3.5 2.24
GHF0054 RC 72 7/01/2022 199902.786 7577828.572 424.286 0 -90 M1 38 39 1 9.85
GHF0054 RC 72 7/01/2022 199902.786 7577828.572 424.286 0 -90 M2 52.5 57 4.5 2.83
GHF0055 RC 71 7/01/2022 199916.928 7577842.714 425.503 0 -90 M1 39.5 42 2.5 4.93
GHF0055 RC 71 7/01/2022 199916.928 7577842.714 425.503 0 -90 M2 54.5 57 2.5 1.95
GHF0056 RC 72 6/01/2022 199931.07 7577856.856 425.642 0 -90 M1 40.5 42.5 2 3.33
GHF0056 RC 72 6/01/2022 199931.07 7577856.856 425.642 0 -90 M2 55 58.5 3.5 3.16
GHF0126 RC 69 7/02/2022 199804.153 7578153.934 414.16 0 -90 M1 47.5 48 0.5 1.16
GHF0127 RC 76 20/01/2022 199790.103 7578135.636 417.01 0 -90 M1 50 51.5 1.5 2.27
GHF0127 RC 76 20/01/2022 199790.103 7578135.636 417.01 0 -90 M2 62 62.5 0.5 0.75
GHF0128 RC 75 20/01/2022 199775.771 7578125.558 417.187 0 -90 M1 50 52.5 2.5 1.23
GHF0128 RC 75 20/01/2022 199775.771 7578125.558 417.187 0 -90 M2 64.5 66 1.5 1.43
GHF0129 RC 76 19/01/2022 199761.31 7578111.349 416.998 0 -90 M1 48.5 49.5 1 9.04
GHF0129 RC 76 19/01/2022 199761.31 7578111.349 416.998 0 -90 M2 63.5 64.5 1 0.93
GHF0130 RC 76 8/02/2022 199747.22 7578097.271 416.216 0 -90 M1 47 48 1 1.73
GHF0130 RC 76 8/02/2022 199747.22 7578097.271 416.216 0 -90 M2 63 66 3 0.75
GHF0131 RC 72 14/02/2022 199732.851 7578082.632 413.043 0 -90 M1 45 45.5 0.5 0.60
GHF0131 RC 72 14/02/2022 199732.851 7578082.632 413.043 0 -90 M2 59.5 62 2.5 1.09
GHF0132 RC 67 7/02/2022 199718.754 7578069.426 408.494 0 -90 M1 39 40.5 1.5 4.31
GHF0132 RC 67 7/02/2022 199718.754 7578069.426 408.494 0 -90 M2 54.5 55 0.5 0.63
GHF0133 RC 59 5/03/2022 199704.794 7578054.844 401.037 0 -90 M1 31 33 2 1.23
GHF0133 RC 59 5/03/2022 199704.794 7578054.844 401.037 0 -90 M2 48 49 1 1.45
GHF0139 RC 66 5/02/2022 199833.058 7578153.021 411.385 0 -90 M2 57.5 58.5 1 0.76
GHF0141 RC 72 6/02/2022 199804.83 7578123.687 414.46 0 -90 M1 48 49.5 1.5 0.94
GHF0141 RC 72 6/02/2022 199804.83 7578123.687 414.46 0 -90 M2 63.5 64 0.5 0.67
GHF0142 RC 74 21/01/2022 199789.54 7578110.693 415.497 0 -90 M1 48 49.5 1.5 2.20
GHF0142 RC 74 21/01/2022 199789.54 7578110.693 415.497 0 -90 M2 63 65.5 2.5 0.99
GHF0143 RC 76 24/01/2022 199775.305 7578098.687 416.087 0 -90 M1 47.5 48.5 1 4.17
GHF0143 RC 76 24/01/2022 199775.305 7578098.687 416.087 0 -90 M2 63.5 64.5 1 4.20
GHF0144 RC 76 9/02/2022 199761.79 7578083.06 415.197 0 -90 M1 46 47 1 13.16
GHF0144 RC 76 9/02/2022 199761.79 7578083.06 415.197 0 -90 M2 62.5 66 3.5 0.98
GHF0145 RC 72 8/02/2022 199747.149 7578068.64 412.924 0 -90 M1 43.5 46 2.5 2.51
GHF0145 RC 72 8/02/2022 199747.149 7578068.64 412.924 0 -90 M2 59.5 62.5 3 0.99
GHF0146 RC 67 14/02/2022 199734.474 7578055.48 408.48 0 -90 M1 40 40.5 0.5 1.61
GHF0146 RC 67 14/02/2022 199734.474 7578055.48 408.48 0 -90 M2 54.5 58 3.5 3.16
GHF0147 RC 60 4/03/2022 199718.936 7578040.702 400.931 0 -90 M1 32.5 34.5 2 2.16
GHF0147 RC 60 4/03/2022 199718.936 7578040.702 400.931 0 -90 M2 47 50.5 3.5 0.81
GHF0150 RC 66 6/02/2022 199846.845 7578139.785 411 0 -90 M1 48.5 49.5 1 2.03
GHF0150 RC 66 6/02/2022 199846.845 7578139.785 411 0 -90 M2 56.5 57 0.5 29.16
GHF0151 RC 68 7/02/2022 199832.961 7578125.073 411.372 0 -90 M1 47 47.5 0.5 2.50
GHF0152 RC 70 6/02/2022 199817.04 7578110.675 412.713 0 -90 M1 47.5 48 0.5 1.94
GHF0152 RC 70 6/02/2022 199817.04 7578110.675 412.713 0 -90 M2 61 63.5 2.5 1.56
GHF0153 RC 72 27/01/2022 199803.045 7578096.592 414.387 0 -90 M1 46 49 3 2.90
GHF0153 RC 72 27/01/2022 199803.045 7578096.592 414.387 0 -90 M2 62.5 63.5 1 2.57
GHF0154 RC 74 23/01/2022 199789.414 7578083.882 414.615 0 -90 M1 45.5 47 1.5 3.44
GHF0154 RC 74 23/01/2022 199789.414 7578083.882 414.615 0 -90 M2 61 63.5 2.5 1.61
GHF0156 RC 71 11/02/2022 199761.119 7578054.926 410.729 0 -90 M1 43.5 45 1.5 3.70
GHF0156 RC 71 11/02/2022 199761.119 7578054.926 410.729 0 -90 M2 57.5 61 3.5 1.17
GHF0157 RC 66 11/02/2022 199747.366 7578040.441 406.129 0 -90 M1 37.5 38.5 1 1.79
GHF0157 RC 66 11/02/2022 199747.366 7578040.441 406.129 0 -90 M2 52.5 55.5 3 0.88
GHF0158 RC 48 1/03/2022 199733.079 7578026.56 400.669 0 -90 M1 33 33.5 0.5 9.42
GHF0158 RC 48 1/03/2022 199733.079 7578026.56 400.669 0 -90 M2 47 48 1 0.81
GHF0160 RC 76 19/01/2022 199689.916 7577984.315 418.023 0 -90 M2 65.5 67 1.5 1.09
GHF0162 RC 66 2/02/2022 199859.521 7578125.674 409.754 0 -90 M1 47.5 49 1.5 5.48
GHF0163 RC 66 2/02/2022 199845.695 7578112.225 410.589 0 -90 M1 46.5 48 1.5 1.92
GHF0163 RC 66 2/02/2022 199845.695 7578112.225 410.589 0 -90 M2 56.5 57 0.5 1.16
GHF0164 RC 69 6/02/2022 199832.417 7578097.792 411.877 0 -90 M1 46.5 48 1.5 2.91
GHF0164 RC 69 6/02/2022 199832.417 7578097.792 411.877 0 -90 M2 61.5 63 1.5 1.23
GHF0165 RC 72 26/01/2022 199817.334 7578083.406 412.759 0 -90 M1 45.5 47 1.5 13.30
GHF0165 RC 72 26/01/2022 199817.334 7578083.406 412.759 0 -90 M2 61 62.5 1.5 3.84

GHF0166 RC 71 23/01/2022 199802.454 7578069.086 412.298 0 -90 M1 44.5 46.5 2 6.70
GHF0166 RC 71 23/01/2022 199802.454 7578069.086 412.298 0 -90 M2 60 61 1 7.51
GHF0167 RC 70 14/02/2022 199789.471 7578052.819 410.204 0 -90 M1 42 45.5 3.5 6.35
GHF0167 RC 70 14/02/2022 199789.471 7578052.819 410.204 0 -90 M2 58.5 61 2.5 1.44
GHF0168 RC 68 23/02/2022 199774.432 7578040.961 407.511 0 -90 M1 39 40 1 1.28
GHF0168 RC 68 23/02/2022 199774.432 7578040.961 407.511 0 -90 M2 54 58 4 1.53
GHF0169 RC 64 23/02/2022 199765.847 7578029.105 404.519 0 -90 M1 37.5 40 2.5 0.68
GHF0169 RC 64 23/02/2022 199765.847 7578029.105 404.519 0 -90 M2 51.5 54.5 3 1.20
GHF0170 RC 59 1/03/2022 199747.221 7578012.418 399.542 0 -90 M1 32 32.5 0.5 2.15
GHF0170 RC 59 1/03/2022 199747.221 7578012.418 399.542 0 -90 M2 46 47.5 1.5 1.08
GHF0172 RC 79 18/01/2022 199705.206 7577970.56 419.926 0 -90 M1 51 52 1 1.05
GHF0172 RC 79 18/01/2022 199705.206 7577970.56 419.926 0 -90 M2 65.5 68 2.5 3.23
GHF0173 RC 78 13/01/2022 199690.37 7577955.321 421.258 0 -90 M1 54.5 56.5 2 1.25
GHF0173 RC 78 13/01/2022 199690.37 7577955.321 421.258 0 -90 M2 67 71.5 4.5 1.70
GHF0175 RC 72 21/02/2022 199662.369 7577927.565 427.552 0 -90 M1 60 61 1 1.26
GHF0175 RC 72 21/02/2022 199662.369 7577927.565 427.552 0 -90 M2 73.5 77 3.5 0.98
GHF0176 RC 87 25/02/2022 199648.226 7577913.423 430.838 0 -90 M1 62.5 64 1.5 8.10
GHF0176 RC 87 25/02/2022 199648.226 7577913.423 430.838 0 -90 M2 73.5 76.5 3 1.66
GHF0177 RC 90 26/02/2022 199634.084 7577899.28 432.894 0 -90 M1 64.5 66 1.5 2.06
GHF0178 RC 96 3/03/2022 199605.8 7577870.996 436.124 0 -90 M1 70 71.5 1.5 3.80
GHF0178 RC 96 3/03/2022 199605.8 7577870.996 436.124 0 -90 M2 84.5 85 0.5 0.51
GHF0179 RC 102 31/03/2022 199577.516 7577842.711 442.788 0 -90 M2 90.5 92.5 2 1.25
GHF0180 RC 108 30/03/2022 199563.374 7577828.569 443.69 0 -90 M1 80 82 2 0.63
GHF0180 RC 108 30/03/2022 199563.374 7577828.569 443.69 0 -90 M2 91.5 92.5 1 1.19
GHF0181 RC 104 26/03/2022 199549.232 7577814.427 439.536 0 -90 M1 72.5 75.5 3 18.50
GHF0181 RC 104 26/03/2022 199549.232 7577814.427 439.536 0 -90 M2 88 88.5 0.5 0.70
GHF0182 RC 100 24/03/2022 199535.09 7577800.285 435.043 0 -90 M1 67.5 69 1.5 8.19
GHF0182 RC 100 24/03/2022 199535.09 7577800.285 435.043 0 -90 M2 88 89 1 0.67
GHF0183 RC 66 6/02/2022 199846.511 7578083.429 409.689 0 -90 M1 44 46.5 2.5 4.97
GHF0183 RC 66 6/02/2022 199846.511 7578083.429 409.689 0 -90 M2 59 60.5 1.5 4.29
GHF0184 RC 48 24/01/2022 199831.934 7578069.736 409.718 0 -90 M1 43.5 44.5 1 3.79
GHF0184 RC 48 24/01/2022 199831.934 7578069.736 409.718 0 -90 M2 56.5 59.5 3 3.70
GHF0185 RC 66 22/01/2022 199818.372 7578055.04 407.717 0 -90 M1 41 43 2 6.38
GHF0185 RC 66 22/01/2022 199818.372 7578055.04 407.717 0 -90 M2 55.5 56.5 1 10.20
GHF0186 RC 65 12/02/2022 199803.115 7578040.548 406.671 0 -90 M1 38.5 39.5 1 2.63
GHF0186 RC 65 12/02/2022 199803.115 7578040.548 406.671 0 -90 M2 54 57 3 1.05
GHF0187 RC 42 24/02/2022 199789.647 7578026.561 404.202 0 -90 M1 35.5 36 0.5 7.42
GHF0187 RC 42 24/02/2022 199789.647 7578026.561 404.202 0 -90 M2 51 54 3 2.24
GHF0188 RC 61 24/02/2022 199775.505 7578012.418 401.772 0 -90 M1 32.5 34.5 2 2.22
GHF0188 RC 61 24/02/2022 199775.505 7578012.418 401.772 0 -90 M2 48 52 4 2.04
GHF0189 RC 58 28/02/2022 199761.363 7577998.276 398.617 0 -90 M1 29.5 30.5 1 6.62
GHF0189 RC 58 28/02/2022 199761.363 7577998.276 398.617 0 -90 M2 44.5 48 3.5 0.55
GHF0190 RC 24 11/01/2022 199731.152 7577969.544 418.66 0 -90 M1 48.5 51 2.5 2.35
GHF0190 RC 24 11/01/2022 199731.152 7577969.544 418.66 0 -90 M2 63 63.5 0.5 0.63
GHF0191 RC 77 10/01/2022 199719.588 7577956.095 420.513 0 -90 M1 51.5 52.5 1 1.39
GHF0191 RC 77 10/01/2022 199719.588 7577956.095 420.513 0 -90 M2 68 70 2 1.12
GHF0192 RC 79 12/01/2022 199705.338 7577942.273 421.605 0 -90 M1 54 56.5 2.5 4.06
GHF0192 RC 79 12/01/2022 199705.338 7577942.273 421.605 0 -90 M2 69 71.5 2.5 2.07
GHF0193 RC 81 19/01/2022 199691.77 7577927.446 424.742 0 -90 M1 57 58.5 1.5 7.96
GHF0193 RC 81 19/01/2022 199691.77 7577927.446 424.742 0 -90 M2 72 74 2 2.34
GHF0194 RC 87 22/02/2022 199676.511 7577913.423 429.304 0 -90 M1 61.5 63 1.5 7.41
GHF0194 RC 87 22/02/2022 199676.511 7577913.423 429.304 0 -90 M2 73.5 75.5 2 0.53
GHF0195 RC 90 24/02/2022 199662.369 7577899.281 434.132 0 -90 M1 66 66.5 0.5 1.15
GHF0195 RC 90 24/02/2022 199662.369 7577899.281 434.132 0 -90 M2 79 80 1 0.88
GHF0196 RC 94 25/02/2022 199648.227 7577885.138 437.501 0 -90 M1 68.5 70.5 2 2.38
GHF0196 RC 94 25/02/2022 199648.227 7577885.138 437.501 0 -90 M2 82 83 1 0.73
GHF0197 RC 98 27/02/2022 199634.085 7577870.996 440.117 0 -90 M1 71 72.5 1.5 1.82
GHF0197 RC 98 27/02/2022 199634.085 7577870.996 440.117 0 -90 M2 88 89 1 1.04
GHF0198 RC 102 4/03/2022 199619.943 7577856.854 442.811 0 -90 M1 78.5 79.5 1 0.60
GHF0198 RC 102 4/03/2022 199619.943 7577856.854 442.811 0 -90 M2 89.5 91 1.5 0.92
GHF0199 RC 110 1/04/2022 199577.517 7577814.427 447.688 0 -90 M1 84 85 1 0.81
GHF0199 RC 110 1/04/2022 199577.517 7577814.427 447.688 0 -90 M2 95 96.5 1.5 1.49
GHF0200 RC 108 30/03/2022 199563.374 7577800.285 443.467 0 -90 M1 75.5 77.5 2 28.14
GHF0200 RC 108 30/03/2022 199563.374 7577800.285 443.467 0 -90 M2 92.5 93 0.5 0.75
GHF0203 RC 59 22/01/2022 199832.809 7578040.582 402.258 0 -90 M1 34 36 2 3.07
GHF0203 RC 59 22/01/2022 199832.809 7578040.582 402.258 0 -90 M2 49.5 52 2.5 1.07
GHF0204 RC 59 26/02/2022 199817.931 7578026.561 402.362 0 -90 M1 33.5 35 1.5 6.42

GHF0204 RC 59 26/02/2022 199817.931 7578026.561 402.362 0 -90 M2 49.5 53.5 4 1.53
GHF0205 RC 54 25/02/2022 199803.789 7578012.419 402.141 0 -90 M1 33.5 35.5 2 13.56
GHF0205 RC 54 25/02/2022 199803.789 7578012.419 402.141 0 -90 M2 49 53 4 0.88
GHF0206 RC 57 28/02/2022 199789.647 7577998.276 399.233 0 -90 M1 28 30 2 5.21
GHF0206 RC 57 28/02/2022 199789.647 7577998.276 399.233 0 -90 M2 45 48 3 0.79
GHF0207 RC 75 9/01/2022 199748.273 7577955.746 419.625 0 -90 M1 48.5 51 2.5 2.05
GHF0207 RC 75 9/01/2022 199748.273 7577955.746 419.625 0 -90 M2 64.5 68 3.5 1.37
GHF0209 RC 78 14/01/2022 199720.192 7577928.468 419.475 0 -90 M1 51 52 1 1.09
GHF0209 RC 78 14/01/2022 199720.192 7577928.468 419.475 0 -90 M2 66 68 2 1.96
GHF0210 RC 79 14/01/2022 199703.409 7577914.606 422.066 0 -90 M1 53.5 54.5 1 2.31
GHF0210 RC 79 14/01/2022 199703.409 7577914.606 422.066 0 -90 M2 67 69 2 1.53
GHF0211 RC 81 18/01/2022 199692.292 7577895.943 422.235 0 -90 M1 53.5 57.5 4 5.19
GHF0211 RC 81 18/01/2022 199692.292 7577895.943 422.235 0 -90 M2 65 66.5 1.5 0.82
GHF0213 RC 107 2/04/2022 199634.085 7577842.712 447.625 0 -90 M1 83.5 84 0.5 1.32
GHF0213 RC 107 2/04/2022 199634.085 7577842.712 447.625 0 -90 M2 97 97.5 0.5 0.72
GHF0214 RC 102 5/03/2022 199619.943 7577828.57 451.361 0 -90 M1 84 85 1 2.25
GHF0214 RC 102 5/03/2022 199619.943 7577828.57 451.361 0 -90 M2 99.5 100.5 1 1.75
GHF0215 RC 113 3/04/2022 199605.801 7577814.427 451.991 0 -90 M1 83 86 3 1.90
GHF0215 RC 113 3/04/2022 199605.801 7577814.427 451.991 0 -90 M2 97.5 100.5 3 0.60
GHF0216 RC 102 6/03/2022 199591.659 7577800.285 450.274 0 -90 M1 82 84.5 2.5 16.16
GHF0216 RC 102 6/03/2022 199591.659 7577800.285 450.274 0 -90 M2 96.5 98.5 2 4.04
GHF0217 RC 108 23/04/2022 199577.517 7577786.143 444.588 0 -90 M1 76 78.5 2.5 7.60
GHF0218 RC 100 27/02/2022 199563.375 7577772.001 439.411 53 -87 M1 70.5 74.5 4 2.22
GHF0219 RC 97 27/02/2022 199549.233 7577757.858 436.235 356 -90 M1 66 68 2 3.51
GHF0219 RC 97 27/02/2022 199549.233 7577757.858 436.235 356 -90 M2 80.5 81.5 1 0.73
GHF0220 RC 114 26/02/2022 199535.091 7577743.716 435.804 0 -90 M1 64 67.5 3.5 3.57
GHF0220 RC 114 26/02/2022 199535.091 7577743.716 435.804 0 -90 M2 80 80.5 0.5 2.30
GHF0222 RC 50 14/04/2022 199888.785 7578069.049 397.286 0 -90 M1 31 32 1 16.28
GHF0226 RC 54 26/02/2022 199832.074 7578012.419 399.433 0 -90 M1 30 31 1 2.92
GHF0226 RC 54 26/02/2022 199832.074 7578012.419 399.433 0 -90 M2 46.5 48.5 2 1.31
GHF0227 RC 54 27/02/2022 199817.932 7577998.277 399.114 0 -90 M1 30 30.5 0.5 0.81
GHF0227 RC 54 27/02/2022 199817.932 7577998.277 399.114 0 -90 M2 45.5 50 4.5 1.65
GHF0228 RC 54 28/02/2022 199803.789 7577984.134 398.493 0 -90 M1 27.5 30 2.5 2.51
GHF0228 RC 54 28/02/2022 199803.789 7577984.134 398.493 0 -90 M2 45 47 2 4.59
GHF0229 RC 74 8/01/2022 199775.478 7577955.646 418.423 0 -90 M1 47 49 2 2.23
GHF0229 RC 74 8/01/2022 199775.478 7577955.646 418.423 0 -90 M2 63 64.5 1.5 2.03
GHF0230 RC 12 8/01/2022 199761.445 7577942.368 418.873 268 -90 M1 46.5 50 3.5 2.37
GHF0230 RC 12 8/01/2022 199761.445 7577942.368 418.873 268 -90 M2 63 66.5 3.5 0.82
GHF0231 RC 78 21/01/2022 199717.215 7577899.898 419.716 358 -89 M1 50 52 2 5.48
GHF0231 RC 78 21/01/2022 199717.215 7577899.898 419.716 358 -89 M2 66 68.5 2.5 0.70
GHF0232 RC 81 15/01/2022 199704.486 7577883.666 422.781 0 -90 M1 53.5 55 1.5 1.50
GHF0232 RC 81 15/01/2022 199704.486 7577883.666 422.781 0 -90 M2 65.5 67 1.5 0.91
GHF0233 RC 94 28/02/2022 199676.511 7577856.854 435.456 0 -90 M1 66.5 68.5 2 0.72
GHF0233 RC 94 28/02/2022 199676.511 7577856.854 435.456 0 -90 M2 79 81 2 0.61
GHF0234 RC 78 1/03/2022 199662.369 7577842.712 440.501 0 -90 M1 71 72.5 1.5 1.65
GHF0234 RC 78 1/03/2022 199662.369 7577842.712 440.501 0 -90 M2 85.5 86.5 1 0.60
GHF0235 RC 106 2/04/2022 199605.801 7577786.143 446.32 0 -90 M1 80 81 1 0.65
GHF0235 RC 106 2/04/2022 199605.801 7577786.143 446.32 0 -90 M2 93 94 1 0.61
GHF0236 RC 102 28/02/2022 199563.375 7577743.716 437.193 173 -89 M1 66.5 69 2.5 8.43
GHF0237 RC 113 28/02/2022 199549.233 7577729.574 436.415 0 -90 M1 67 68 1 1.40
GHF0237 RC 113 28/02/2022 199549.233 7577729.574 436.415 0 -90 M2 81.5 82 0.5 0.86
GHF0238 RC 114 26/02/2022 199535.091 7577715.432 433.516 1 -89 M2 81.5 82 0.5 0.56
GHF0241 RC 54 7/03/2022 199874.5 7578026.561 401.059 0 -90 M1 35.5 36.5 1 0.66
GHF0241 RC 54 7/03/2022 199874.5 7578026.561 401.059 0 -90 M2 44.5 45 0.5 1.13
GHF0242 RC 52 6/03/2022 199860.358 7578012.419 397.61 0 -90 M1 29 30 1 3.18
GHF0242 RC 52 6/03/2022 199860.358 7578012.419 397.61 0 -90 M2 44.5 45.5 1 0.94
GHF0243 RC 52 5/03/2022 199846.216 7577998.277 398.097 0 -90 M1 28 29.5 1.5 1.25
GHF0243 RC 52 5/03/2022 199846.216 7577998.277 398.097 0 -90 M2 45 46 1 1.86
GHF0244 RC 70 20/01/2022 199789.343 7577943.675 415.972 0 -90 M1 43.5 45.5 2 7.64
GHF0244 RC 70 20/01/2022 199789.343 7577943.675 415.972 0 -90 M2 60.5 62.5 2 2.38
GHF0245 RC 70 21/01/2022 199778.266 7577929.795 414.84 0 -90 M1 43.5 44.5 1 6.12
GHF0245 RC 70 21/01/2022 199778.266 7577929.795 414.84 0 -90 M2 58.5 62 3.5 5.07
GHF0247 RC 82 16/01/2022 199717.288 7577873.067 423.226 0 -90 M1 54 55 1 5.48
GHF0247 RC 82 16/01/2022 199717.288 7577873.067 423.226 0 -90 M2 65.5 68.5 3 1.45
GHF0248 RC 87 22/02/2022 199591.194 7577742.56 428.831 0 -90 M1 59 62.5 3.5 3.88
GHF0248 RC 87 22/02/2022 199591.194 7577742.56 428.831 0 -90 M2 74.5 75 0.5 0.50
GHF0249 RC 109 22/02/2022 199563.375 7577715.432 434.624 11 -90 M1 62 65.5 3.5 1.99

GHF0249 RC 109 22/02/2022 199563.375 7577715.432 434.624 11 -90 M2 79 80 1 0.51
GHF0250 RC 128 22/02/2022 199549.233 7577701.29 432.659 116 -90 M1 69 70 1 3.35
GHF0250 RC 128 22/02/2022 199549.233 7577701.29 432.659 116 -90 M2 81 81.5 0.5 0.61
GHF0252 RC 50 7/03/2022 199888.642 7578012.419 398.386 0 -90 M1 30.5 31 0.5 0.51
GHF0257 RC 62 20/01/2022 199790.192 7577917.651 409.494 0 -90 M1 38.5 39.5 1 8.41
GHF0257 RC 62 20/01/2022 199790.192 7577917.651 409.494 0 -90 M2 52.5 56 3.5 3.08
GHF0258 RC 62 22/01/2022 199775.271 7577898.078 405.698 0 -90 M1 32.5 36 3.5 1.39
GHF0258 RC 62 22/01/2022 199775.271 7577898.078 405.698 0 -90 M2 52 52.5 0.5 3.27
GHF0259 RC 81 16/01/2022 199706.722 7577827.987 425.18 0 -90 M1 55.5 58.5 3 1.80
GHF0259 RC 81 16/01/2022 199706.722 7577827.987 425.18 0 -90 M2 67.5 69 1.5 0.51
GHF0260 RC 87 16/02/2022 199690.654 7577814.428 430.981 0 -90 M1 60 61.5 1.5 6.98
GHF0260 RC 87 16/02/2022 199690.654 7577814.428 430.981 0 -90 M2 75.5 76.5 1 2.20
GHF0261 RC 93 8/03/2022 199648.227 7577772.001 436.49 0 -90 M2 80 83 3 6.82
GHF0262 RC 85 19/02/2022 199619.873 7577742.739 427.872 0 -90 M1 60.5 61.5 1 0.96
GHF0262 RC 85 19/02/2022 199619.873 7577742.739 427.872 0 -90 M2 71 73 2 0.62
GHF0263 RC 101 8/01/2022 199591.135 7577713.849 428.411 0 -90 M1 56.5 58.5 2 1.12
GHF0263 RC 101 8/01/2022 199591.135 7577713.849 428.411 0 -90 M2 75.5 76 0.5 1.46
GHF0264 RC 105 22/02/2022 199577.517 7577701.29 432.984 356 -90 M1 59.5 61.5 2 0.73
GHF0264 RC 105 22/02/2022 199577.517 7577701.29 432.984 356 -90 M2 77 78 1 0.76
GHF0267 RC 55 13/04/2022 199902.784 7577998.277 401.715 0 -90 M1 32.5 33.5 1 4.24
GHF0267 RC 55 13/04/2022 199902.784 7577998.277 401.715 0 -90 M2 43.5 44.5 1 0.59
GHF0268 RC 58 11/01/2022 199889.163 7577984.147 403.212 0 -90 M1 32 36.5 4.5 3.20
GHF0268 RC 58 11/01/2022 199889.163 7577984.147 403.212 0 -90 M2 45.5 47 1.5 1.31
GHF0269 RC 54 10/01/2022 199875.235 7577969.319 403.719 0 -90 M1 30 35.5 5.5 16.02
GHF0269 RC 54 10/01/2022 199875.235 7577969.319 403.719 0 -90 M2 42.5 45 2.5 0.59
GHF0270 RC 57 10/01/2022 199860.243 7577956.677 405.086 0 -90 M1 32 35 3 3.82
GHF0270 RC 57 10/01/2022 199860.243 7577956.677 405.086 0 -90 M2 48 50 2 0.55
GHF0271 RC 59 10/01/2022 199846.011 7577941.92 406.302 0 -90 M1 31.5 34 2.5 1.99
GHF0271 RC 59 10/01/2022 199846.011 7577941.92 406.302 0 -90 M2 48.5 52 3.5 3.57
GHF0273 RC 61 22/01/2022 199790.4 7577884.438 406.604 0 -90 M1 32 36.5 4.5 4.86
GHF0273 RC 61 22/01/2022 199790.4 7577884.438 406.604 0 -90 M2 51.5 52.5 1 1.60
GHF0274 RC 63 23/01/2022 199776.85 7577871.998 407.656 0 -90 M1 34 37 3 10.74
GHF0274 RC 63 23/01/2022 199776.85 7577871.998 407.656 0 -90 M2 46 49 3 1.77
GHF0275 RC 68 23/01/2022 199762.373 7577857.338 412.209 0 -90 M1 41 42.5 1.5 4.30
GHF0275 RC 68 23/01/2022 199762.373 7577857.338 412.209 0 -90 M2 53 55.5 2.5 0.91
GHF0276 RC 74 24/01/2022 199748.123 7577842.823 418.374 0 -90 M1 45.5 47.5 2 1.01
GHF0276 RC 74 24/01/2022 199748.123 7577842.823 418.374 0 -90 M2 58.5 61.5 3 1.73
GHF0277 RC 77 17/01/2022 199734.757 7577827.903 422.747 0 -90 M1 53 55 2 0.59
GHF0277 RC 77 17/01/2022 199734.757 7577827.903 422.747 0 -90 M2 63.5 67 3.5 2.25
GHF0278 RC 79 17/01/2022 199719.396 7577813.552 425.392 0 -90 M1 56 56.5 0.5 0.86
GHF0279 RC 54 1/02/2022 199704.796 7577800.286 425.316 0 -90 M1 52 53.5 1.5 1.09
GHF0281 RC 88 9/03/2022 199648.228 7577743.717 431.083 0 -90 M1 63 64 1 0.68
GHF0281 RC 88 9/03/2022 199648.228 7577743.717 431.083 0 -90 M2 74 75 1 1.09
GHF0282 RC 18 17/02/2022 199635.379 7577731.533 428.039 0 -90 M1 59.5 60.5 1 1.38
GHF0282 RC 18 17/02/2022 199635.379 7577731.533 428.039 0 -90 M2 71 72 1 0.68
GHF0283 RC 18 5/01/2022 199619.453 7577714.29 420.499 0 -90 M2 64 65.5 1.5 0.57
GHF0284 RC 54 6/01/2022 199605.483 7577702.442 425.706 0 -90 M1 53 53.5 0.5 0.82
GHF0284 RC 54 6/01/2022 199605.483 7577702.442 425.706 0 -90 M2 70.5 73 2.5 0.79
GHF0285 RC 100 22/02/2022 199591.66 7577687.148 430.643 14 -89 M1 57.5 59.5 2 3.03
GHF0285 RC 100 22/02/2022 199591.66 7577687.148 430.643 14 -89 M2 75 76 1 0.59
GHF0287 RC 36 11/01/2022 199902.842 7577969.975 405.234 0 -90 M1 32 35.5 3.5 2.11
GHF0287 RC 36 11/01/2022 199902.842 7577969.975 405.234 0 -90 M2 46 46.5 0.5 0.67
GHF0289 RC 67 15/01/2022 199874.093 7577940.67 414.633 0 -90 M1 39 41.5 2.5 4.15
GHF0289 RC 67 15/01/2022 199874.093 7577940.67 414.633 0 -90 M2 57 59.5 2.5 3.09
GHF0292 RC 61 23/01/2022 199790.217 7577857.613 407.119 0 -90 M1 32.5 34.5 2 2.11
GHF0292 RC 61 23/01/2022 199790.217 7577857.613 407.119 0 -90 M2 46.5 48 1.5 1.40
GHF0293 RC 73 18/04/2022 199733.08 7577800.286 420.552 0 -90 M1 47.5 48 0.5 15.94
GHF0294 RC 72 17/01/2022 199719.734 7577786.547 419.481 0 -90 M1 44 45 1 1.99
GHF0294 RC 72 17/01/2022 199719.734 7577786.547 419.481 0 -90 M2 61.5 63 1.5 1.29
GHF0295 RC 82 13/04/2022 199676.512 7577743.717 427.558 0 -90 M2 69 70 1 3.83
GHF0296 RC 72 5/01/2022 199635.586 7577701.245 420.188 0 -90 M1 46.5 47 0.5 8.27
GHF0296 RC 72 5/01/2022 199635.586 7577701.245 420.188 0 -90 M2 62.5 64.5 2 1.10
GHF0297 RC 90 4/01/2022 199621.655 7577686.293 425.847 0 -90 M1 51 53.5 2.5 5.54
GHF0297 RC 90 4/01/2022 199621.655 7577686.293 425.847 0 -90 M2 69.5 71 1.5 0.67
GHF0298 RC 55 12/01/2022 199917.105 7577955.396 407.079 0 -90 M1 32 37 5 4.36
GHF0298 RC 55 12/01/2022 199917.105 7577955.396 407.079 0 -90 M2 46.5 47.5 1 0.89
GHF0299 RC 66 13/01/2022 199900.989 7577939.504 417.62 0 -90 M1 41 43.5 2.5 2.81

GHF0299 RC 66 13/01/2022 199900.989 7577939.504 417.62 0 -90 M2 55 56 1 0.65
GHF0300 RC 42 15/01/2022 199887.855 7577926.165 418.699 0 -90 M1 42 44.5 2.5 1.62
GHF0300 RC 42 15/01/2022 199887.855 7577926.165 418.699 0 -90 M2 60 62.5 2.5 0.84
GHF0301 RC 48 17/01/2022 199733.262 7577772.181 414.558 0 -90 M1 38 39.5 1.5 16.39
GHF0302 RC 68 16/01/2022 199718.483 7577757.553 414.696 0 -90 M1 38.5 40 1.5 4.65
GHF0302 RC 68 16/01/2022 199718.483 7577757.553 414.696 0 -90 M2 53.5 55.5 2 2.71
GHF0303 RC 72 15/02/2022 199704.349 7577743.437 418.872 0 -90 M2 58.5 59.5 1 5.15
GHF0304 RC 60 15/02/2022 199691.468 7577729.872 420.143 0 -90 M1 48 50.5 2.5 0.64
GHF0304 RC 60 15/02/2022 199691.468 7577729.872 420.143 0 -90 M2 59.5 61 1.5 2.76
GHF0306 RC 71 3/01/2022 199662.35 7577701.255 419.362 0 -90 M1 48 49 1 0.65
GHF0306 RC 71 3/01/2022 199662.35 7577701.255 419.362 0 -90 M2 60 60.5 0.5 1.07
GHF0307 RC 30 3/01/2022 199930.955 7577941.658 409.248 0 -90 M1 33 35 2 1.51
GHF0308 RC 42 13/01/2022 199916.278 7577926.471 418.396 0 -90 M1 40 42.5 2.5 1.81
GHF0308 RC 42 13/01/2022 199916.278 7577926.471 418.396 0 -90 M2 54 57 3 0.96
GHF0309 RC 69 2/01/2022 199705.214 7577715.027 417.997 0 -90 M1 44.5 46.5 2 1.38
GHF0309 RC 69 2/01/2022 199705.214 7577715.027 417.997 0 -90 M2 55.5 57.5 2 2.92
GHF0310 RC 78 2/01/2022 199691.154 7577701.452 420.329 0 -90 M1 47 48.5 1.5 3.19
GHF0310 RC 78 2/01/2022 199691.154 7577701.452 420.329 0 -90 M2 59 60 1 1.91
GHF0311 RC 60 13/01/2022 199945.275 7577925.882 415.786 0 -90 M1 36 39.5 3.5 3.07
GHF0313 RC 67 14/01/2022 199930.311 7577912.472 420.51 0 -90 M1 40.5 42.5 2 3.13
GHF0313 RC 67 14/01/2022 199930.311 7577912.472 420.51 0 -90 M2 54 56.5 2.5 1.14
GHF0323 RC 102 16/04/2022 199506.805 7577998.274 432.246 0 -90 M1 63 63.5 0.5 0.51
GHF0323 RC 102 16/04/2022 199506.805 7577998.274 432.246 0 -90 M2 77 78.5 1.5 0.98
GHF0326 RC 101 17/04/2022 199520.947 7578012.417 431.12 0 -90 M1 65.5 67 1.5 2.82
GHF0326 RC 101 17/04/2022 199520.947 7578012.417 431.12 0 -90 M2 76.5 78 1.5 1.12
GHF0327 RC 102 15/04/2022 199535.089 7577998.275 435.161 0 -90 M1 66.5 67.5 1 1.36
GHF0327 RC 102 15/04/2022 199535.089 7577998.275 435.161 0 -90 M2 80.5 82 1.5 1.58
GHF0330 RC 88 19/04/2022 199535.089 7578026.559 428.475 0 -90 M1 61.5 63 1.5 0.59
GHF0330 RC 88 19/04/2022 199535.089 7578026.559 428.475 0 -90 M2 73 74.5 1.5 1.35
GHF0331 RC 92 18/04/2022 199549.231 7578012.417 431.748 0 -90 M1 63.5 64 0.5 1.07
GHF0331 RC 92 18/04/2022 199549.231 7578012.417 431.748 0 -90 M2 77 78.5 1.5 1.34
GHF0335 RC 80 19/04/2022 199549.231 7578040.701 425.46 0 -90 M1 59.5 61.5 2 1.12
GHF0335 RC 80 19/04/2022 199549.231 7578040.701 425.46 0 -90 M2 71 73 2 0.55
GHF0336 RC 88 21/04/2022 199563.373 7578026.559 427.779 0 -90 M1 60 62.5 2.5 0.86
GHF0336 RC 88 21/04/2022 199563.373 7578026.559 427.779 0 -90 M2 71.5 74 2.5 0.57
GHF0337 RC 85 21/04/2022 199577.515 7578012.417 425.027 0 -90 M1 57.5 58 0.5 1.32
GHF0337 RC 85 21/04/2022 199577.515 7578012.417 425.027 0 -90 M2 71 72 1 1.33
GHF0338 RC 80 23/04/2022 199591.657 7577998.275 419.756 0 -90 M1 52 52.5 0.5 1.25
GHF0338 RC 80 23/04/2022 199591.657 7577998.275 419.756 0 -90 M2 64.5 67 2.5 1.59
GHF0345 RC 82 20/04/2022 199577.515 7578040.701 422.338 0 -90 M1 57.5 58.5 1 1.12
GHF0345 RC 82 20/04/2022 199577.515 7578040.701 422.338 0 -90 M2 70.5 71 0.5 0.81
GHF0346 RC 81 27/04/2022 199591.657 7578026.559 421.037 0 -90 M1 55.5 56 0.5 1.32
GHF0346 RC 81 27/04/2022 199591.657 7578026.559 421.037 0 -90 M2 67.5 69 1.5 0.68
GHF0347 RC 79 24/04/2022 199605.799 7578012.417 419.416 0 -90 M1 52.5 53.5 1 0.90
GHF0347 RC 79 24/04/2022 199605.799 7578012.417 419.416 0 -90 M2 66.5 68.5 2 1.07
GHF0355 RC 79 29/04/2022 199605.799 7578040.702 418.662 0 -90 M1 51.5 52.5 1 1.13
GHF0355 RC 79 29/04/2022 199605.799 7578040.702 418.662 0 -90 M2 65 66.5 1.5 0.87
GHF0356 RC 76 25/04/2022 199619.941 7578026.56 415.707 0 -90 M1 50 51 1 0.54
GHF0364 RC 76 28/04/2022 199619.941 7578054.844 415.905 0 -90 M1 46.5 48 1.5 1.32
GHF0364 RC 76 28/04/2022 199619.941 7578054.844 415.905 0 -90 M2 62.5 64 1.5 0.79
GHF0365 RC 73 28/04/2022 199634.083 7578040.702 413.313 0 -90 M2 60.5 61.5 1 1.07
GHF0380 RC 62 30/04/2022 199676.51 7578054.844 401.581 0 -90 M1 32.5 34 1.5 1.07
GHF0380 RC 62 30/04/2022 199676.51 7578054.844 401.581 0 -90 M2 48.5 49 0.5 1.36
GHF0381 RC 72 20/03/2022 199520.945 7578238.691 411.775 0 -90 M1 44 45.5 1.5 0.68
GHF0381 RC 72 20/03/2022 199520.945 7578238.691 411.775 0 -90 M2 58.5 59.5 1 5.36
GHF0382 RC 78 15/03/2022 199577.514 7578182.123 417.882 343 -89 M1 45.5 46 0.5 1.71
GHF0382 RC 78 15/03/2022 199577.514 7578182.123 417.882 343 -89 M2 59 63 4 1.00
GHF0386 RC 60 15/04/2022 199676.51 7578083.128 400.046 0 -90 M1 30.5 31.5 1 0.60
GHF0386 RC 60 15/04/2022 199676.51 7578083.128 400.046 0 -90 M2 45.5 47.5 2 1.02
GHF0389 RC 73 24/03/2022 199506.803 7578281.117 413.485 0 -90 M1 47 47.5 0.5 1.28
GHF0389 RC 73 24/03/2022 199506.803 7578281.117 413.485 0 -90 M2 58 59.5 1.5 0.93
GHF0390 RC 73.5 24/03/2022 199520.945 7578266.975 413.258 344 -89 M1 46.5 47.5 1 0.71
GHF0390 RC 73.5 24/03/2022 199520.945 7578266.975 413.258 344 -89 M2 57.5 60 2.5 1.09
GHF0391 RC 74 20/03/2022 199535.087 7578252.833 413.605 0 -90 M1 46 47.5 1.5 1.72
GHF0391 RC 74 20/03/2022 199535.087 7578252.833 413.605 0 -90 M2 58.5 60 1.5 2.08
GHF0393 RC 80 20/03/2022 199591.656 7578196.265 420.068 0 -90 M2 61 63 2 1.43
GHF0397 RC 70 24/03/2022 199549.229 7578266.975 415.171 1 -90 M2 59.5 60.5 1 1.99

GHF0398 RC 71 14/03/2022 199577.514 7578238.691 415.53 114 -90 M1 43.5 45 1.5 2.10
GHF0398 RC 71 14/03/2022 199577.514 7578238.691 415.53 114 -90 M2 56 58 2 1.74
GHF0399 RC 88 29/03/2002 199591.656 7578224.549 418.316 0 -90 M1 48.5 49 0.5 1.04
GHF0399 RC 88 29/03/2002 199591.656 7578224.549 418.316 0 -90 M2 59 62.5 3.5 1.81
GHF0400 RC 78 13/04/2022 199605.798 7578210.407 423.241 0 -90 M1 51 54.5 3.5 0.90
GHF0400 RC 78 13/04/2022 199605.798 7578210.407 423.241 0 -90 M2 64.5 66.5 2 1.17
GHF0401 RC 82 7/03/2022 199619.94 7578196.265 426.942 0 -90 M1 55 56 1 0.74
GHF0401 RC 82 7/03/2022 199619.94 7578196.265 426.942 0 -90 M2 69 70.5 1.5 1.53
GHF0402 RC 90 4/03/2022 199648.225 7578167.981 419.754 7 -89 M1 47.5 50.5 3 1.23
GHF0402 RC 90 4/03/2022 199648.225 7578167.981 419.754 7 -89 M2 63 64.5 1.5 1.75
GHF0403 RC 78 4/03/2022 199662.367 7578153.839 418.102 355 -89 M1 46 47 1 0.70
GHF0403 RC 78 4/03/2022 199662.367 7578153.839 418.102 355 -89 M2 60.5 62.5 2 3.23
GHF0404 RC 83 4/03/2022 199676.509 7578139.697 418.611 316 -90 M1 47 49 2 1.85
GHF0404 RC 83 4/03/2022 199676.509 7578139.697 418.611 316 -90 M2 63 66 3 1.32
GHF0405 RC 78 4/03/2022 199690.651 7578125.555 417.828 51 -89 M1 47 48 1 3.33
GHF0405 RC 78 4/03/2022 199690.651 7578125.555 417.828 51 -89 M2 64 66.5 2.5 0.71
GHF0406 RC 77 4/03/2022 199704.794 7578111.413 416.605 306 -90 M1 46 49.5 3.5 2.07
GHF0406 RC 77 4/03/2022 199704.794 7578111.413 416.605 306 -90 M2 61.5 64.5 3 0.88
GHF0407 RC 84 4/03/2022 199718.936 7578097.271 414.531 0 -90 M1 45 45.5 0.5 2.23
GHF0407 RC 84 4/03/2022 199718.936 7578097.271 414.531 0 -90 M2 61 63 2 1.03
GHF0408 RC 82 18/04/2022 199506.802 7578337.686 427.377 0 -90 M1 57.5 58 0.5 0.75
GHF0409 RC 80 18/04/2022 199535.087 7578309.402 424.945 0 -90 M1 54 56 2 1.93
GHF0409 RC 80 18/04/2022 199535.087 7578309.402 424.945 0 -90 M2 67.5 68 0.5 3.00
GHF0411 RC 72 15/04/2022 199591.656 7578252.833 417.185 0 -90 M1 47.5 48.5 1 2.64
GHF0411 RC 72 15/04/2022 199591.656 7578252.833 417.185 0 -90 M2 57 58 1 0.68
GHF0412 RC 76 30/03/2022 199605.798 7578238.691 420.611 2 -89 M1 48 49 1 0.97
GHF0412 RC 76 30/03/2022 199605.798 7578238.691 420.611 2 -89 M2 60.5 61.5 1 2.14
GHF0413 RC 80 13/04/2022 199619.94 7578224.549 424.978 183 -90 M1 52 54 2 1.88
GHF0413 RC 80 13/04/2022 199619.94 7578224.549 424.978 183 -90 M2 65.5 68 2.5 3.19
GHF0414 RC 82 5/03/2022 199634.082 7578210.407 426.576 1 -89 M1 54 55.5 1.5 0.91
GHF0414 RC 82 5/03/2022 199634.082 7578210.407 426.576 1 -89 M2 68.5 70.5 2 2.64
GHF0415 RC 81 18/04/2022 199648.225 7578196.265 425.101 138 -90 M1 53 55 2 0.58
GHF0415 RC 81 18/04/2022 199648.225 7578196.265 425.101 138 -90 M2 68.5 70.5 2 3.38
GHF0416 RC 78 5/03/2022 199662.367 7578182.123 422.544 2 -90 M1 51 52 1 1.65
GHF0416 RC 78 5/03/2022 199662.367 7578182.123 422.544 2 -90 M2 65.5 68 2.5 2.71
GHF0417 RC 81 5/03/2022 199676.509 7578167.981 420.989 2 -89 M2 64 66.5 2.5 2.13
GHF0419 RC 79 4/03/2022 199704.793 7578139.697 419.127 0 -90 M1 48 49 1 3.36
GHF0419 RC 79 4/03/2022 199704.793 7578139.697 419.127 0 -90 M2 64 65 1 0.93
GHF0420 RC 78 27/05/2022 199718.936 7578125.555 417.795 344 -89 M1 46.5 48 1.5 0.53
GHF0420 RC 78 27/05/2022 199718.936 7578125.555 417.795 344 -89 M2 63.5 64.5 1 2.91
GHF0422 RC 88 18/04/2022 199520.944 7578351.828 432.839 3 -90 M1 62 63.5 1.5 5.08
GHF0422 RC 88 18/04/2022 199520.944 7578351.828 432.839 3 -90 M2 73.5 75.5 2 2.48
GHF0423 RC 85 18/04/2022 199535.086 7578337.686 430.377 344 -89 M2 71.5 72 0.5 1.61
GHF0424 RC 81 18/04/2022 199549.229 7578323.544 425.793 10 -89 M1 54.5 55.5 1 5.77
GHF0424 RC 81 18/04/2022 199549.229 7578323.544 425.793 10 -89 M2 67 67.5 0.5 4.15
GHF0426 RC 75 13/04/2022 199605.798 7578266.976 419.674 310 -90 M1 49.5 50.5 1 2.22
GHF0426 RC 75 13/04/2022 199605.798 7578266.976 419.674 310 -90 M2 62 62.5 0.5 2.51
GHF0427 RC 78 7/03/2022 199619.94 7578252.834 422.937 0 -90 M1 51 52 1 2.84
GHF0427 RC 78 7/03/2022 199619.94 7578252.834 422.937 0 -90 M2 62.5 65 2.5 1.71
GHF0428 RC 75 23/04/2022 199662.367 7578210.408 420.444 0 -90 M1 47.5 49.5 2 2.72
GHF0428 RC 75 23/04/2022 199662.367 7578210.408 420.444 0 -90 M2 61.5 62.5 1 1.31
GHF0429 RC 79 24/04/2022 199676.509 7578196.266 418.877 305 -89 M1 46.5 48.5 2 2.36
GHF0429 RC 79 24/04/2022 199676.509 7578196.266 418.877 305 -89 M2 61.5 62.5 1 3.08
GHF0430 RC 79 24/04/2022 199690.651 7578182.124 418.964 162 -89 M1 46.5 48.5 2 1.58
GHF0430 RC 79 24/04/2022 199690.651 7578182.124 418.964 162 -89 M2 63 64.5 1.5 1.89
GHF0431 RC 82 1/05/2022 199704.793 7578167.981 420.582 318 -89 M1 48.5 49.5 1 2.59
GHF0431 RC 82 1/05/2022 199704.793 7578167.981 420.582 318 -89 M2 63.5 67.5 4 0.85
GHF0432 RC 82 26/04/2022 199718.935 7578153.839 422.534 0 -90 M1 50.5 54.5 4 1.96
GHF0432 RC 82 26/04/2022 199718.935 7578153.839 422.534 0 -90 M2 67 69 2 2.13
GHF0433 RC 78 11/02/2022 199733.078 7578139.697 418.774 0 -90 M1 49 51 2 2.39
GHF0433 RC 78 11/02/2022 199733.078 7578139.697 418.774 0 -90 M2 64.5 65.5 1 2.46
GHF0434 RC 78 20/02/2022 199747.22 7578125.555 417.878 0 -90 M1 48 49 1 2.07
GHF0434 RC 78 20/02/2022 199747.22 7578125.555 417.878 0 -90 M2 63 65 2 0.96
GHF0435 RC 88 18/04/2022 199535.086 7578365.97 433.443 356 -89 M2 71.5 73 1.5 2.62
GHF0436 RC 84 18/04/2022 199549.228 7578351.828 429 4 -89 M2 68 69 1 0.76
GHF0438 RC 90 14/03/2022 199591.655 7578309.402 416.627 310 -90 M1 44.5 45.5 1 1.13
GHF0438 RC 90 14/03/2022 199591.655 7578309.402 416.627 310 -90 M2 55 55.5 0.5 0.91

GHF0440 RC 77 7/03/2022 199634.082 7578266.976 421.545 349 -89 M1 49.5 51 1.5 6.19
GHF0440 RC 77 7/03/2022 199634.082 7578266.976 421.545 349 -89 M2 61 62 1 1.79
GHF0441 RC 72 23/04/2022 199662.366 7578238.692 416.711 0 -90 M2 58 59 1 3.01
GHF0443 RC 79 23/04/2022 199690.651 7578210.408 415.969 1 -88 M1 45 45.5 0.5 1.89
GHF0443 RC 79 23/04/2022 199690.651 7578210.408 415.969 1 -88 M2 58.5 60 1.5 0.75
GHF0444 RC 79 26/04/2022 199704.793 7578196.266 417.126 16 -88 M1 45.5 47 1.5 1.35
GHF0444 RC 79 26/04/2022 199704.793 7578196.266 417.126 16 -88 M2 60.5 62 1.5 4.47
GHF0445 RC 79 4/03/2022 199718.935 7578182.124 417.588 0 -90 M1 46.5 48.5 2 1.11
GHF0445 RC 79 4/03/2022 199718.935 7578182.124 417.588 0 -90 M2 62 64.5 2.5 2.00
GHF0446 RC 79 25/04/2022 199733.078 7578167.982 418.669 310 -89 M1 47 49 2 0.97
GHF0447 RC 79 21/04/2022 199747.22 7578153.84 422.86 360 -89 M1 52.5 55 2.5 3.03
GHF0447 RC 79 21/04/2022 199747.22 7578153.84 422.86 360 -89 M2 67.5 68 0.5 1.64
GHF0452 RC 81 7/03/2022 199634.082 7578295.26 425.547 6 -89 M1 53 53.5 0.5 0.61
GHF0453 RC 70.5 1/05/2022 199690.651 7578238.692 416.446 7 -90 M2 56.5 59 2.5 2.33
GHF0454 RC 78.5 22/04/2022 199704.793 7578224.55 413.804 0 -90 M1 42 42.5 0.5 9.36
GHF0455 RC 68 22/04/2022 199718.935 7578210.408 413.026 301 -90 M2 54.5 55 0.5 0.54
GHF0456 RC 79 22/04/2022 199733.077 7578196.266 415.403 348 -90 M1 45 46 1 5.41
GHF0456 RC 79 22/04/2022 199733.077 7578196.266 415.403 348 -90 M2 57 57.5 0.5 1.36
GHF0457 RC 78 3/03/2022 199747.22 7578182.124 416.194 0 -90 M1 47.5 48.5 1 33.16
GHF0458 RC 79.5 25/04/2022 199761.362 7578167.982 417.861 359 -89 M1 48.5 49.5 1 0.87
GHF0459 RC 77 26/04/2022 199775.504 7578153.84 422.371 72 -89 M1 55 56 1 3.11
GHF0460 RC 70 15/04/2022 199605.797 7578351.829 420.307 0 -90 M2 55 55.5 0.5 1.08
GHF0464 RC 71 29/05/2022 199704.793 7578252.834 420.683 159 -90 M1 47 47.5 0.5 17.60
GHF0468 RC 78 2/03/2022 199775.504 7578182.124 414.321 0 -90 M1 48 49 1 0.97
GHF0469 RC 83 15/04/2022 199634.081 7578351.829 427.603 0 -90 M1 51.5 52 0.5 1.44
GHF0470 RC 86 9/03/2022 199648.224 7578337.687 431.044 19 -89 M2 61.5 62.5 1 0.62
GHF0475 RC 73.5 30/04/2022 199747.219 7578238.692 417.911 28 -90 M1 48 50 2 3.04
GHF0479 RC 79 12/03/2022 199690.65 7578323.545 429.361 11 -89 M2 56 56.5 0.5 1.43
GHF0480 RC 80 12/03/2022 199704.792 7578309.403 430.13 7 -90 M2 56.5 57.5 1 0.59
GHF0481 RC 80 12/03/2022 199718.934 7578295.261 430.22 14 -89 M2 57.5 58 0.5 1.29
GHF0482 RC 79 12/03/2022 199733.077 7578281.119 429.084 8 -90 M2 56.5 57 0.5 0.56
GHF0490 RC 68 7/02/2022 199931.069 7577899.282 423.857 174 -90 M1 41.5 44 2.5 17.66
GHF0490 RC 68 7/02/2022 199931.069 7577899.282 423.857 174 -90 M2 60 61.5 1.5 1.66
GHF0491 RC 67 15/02/2022 199938.049 7577892.296 424.172 69 -90 M1 41.5 43.5 2 2.67
GHF0491 RC 67 15/02/2022 199938.049 7577892.296 424.172 69 -90 M2 59.5 61 1.5 1.30
GHF0492 RC 70 17/02/2022 199909.54 7577906.463 422.864 67 -90 M1 42 45 3 2.83
GHF0492 RC 70 17/02/2022 199909.54 7577906.463 422.864 67 -90 M2 60.5 63 2.5 2.44
GHF0494 RC 69.5 17/02/2022 199895.756 7577906.314 422.087 283 -89 M1 42 45 3 5.96
GHF0494 RC 69.5 17/02/2022 199895.756 7577906.314 422.087 283 -89 M2 59.5 62.5 3 2.21
GHF0495 RC 70.5 17/02/2022 199902.657 7577899.5 423.217 3 -89 M1 42 44.5 2.5 8.71
GHF0495 RC 70.5 17/02/2022 199902.657 7577899.5 423.217 3 -89 M2 59.5 63 3.5 2.54
GHF0496 RC 71.5 17/02/2022 199909.675 7577892.491 424.654 3 -88 M1 43.5 44.5 1 15.63
GHF0496 RC 71.5 17/02/2022 199909.675 7577892.491 424.654 3 -88 M2 59.5 63 3.5 7.88
GHF0497 RC 71 17/02/2022 199916.84 7577885.128 425.895 165 -89 M1 43.5 45 1.5 3.35
GHF0497 RC 71 17/02/2022 199916.84 7577885.128 425.895 165 -89 M2 60.5 63.5 3 3.85
GHF0498 RC 70.5 17/02/2022 199924.03 7577877.888 426.759 7 -90 M1 43.5 45 1.5 31.29
GHF0498 RC 70.5 17/02/2022 199924.03 7577877.888 426.759 7 -90 M2 58.5 61.5 3 6.22
GHF0499 RC 69 17/02/2022 199923.876 7577863.732 426.87 359 -89 M1 42 44 2 4.58
GHF0499 RC 69 17/02/2022 199923.876 7577863.732 426.87 359 -89 M2 56.5 61.5 5 2.88
GHF0500 RC 69 17/02/2022 199909.211 7577863.348 426.862 80 -89 M1 42.5 44 1.5 48.84
GHF0500 RC 69 17/02/2022 199909.211 7577863.348 426.862 80 -89 M2 56.5 61.5 5 3.78
GHF0501 RC 68.5 17/02/2022 199916.946 7577856.679 426.95 2 -90 M1 42 44 2 8.90
GHF0501 RC 68.5 17/02/2022 199916.946 7577856.679 426.95 2 -90 M2 56.5 58.5 2 1.56
GHF0502 RC 65.5 17/02/2022 199924.163 7577849.551 425.879 306 -89 M1 40 42 2 3.40
GHF0502 RC 65.5 17/02/2022 199924.163 7577849.551 425.879 306 -89 M2 54 58.5 4.5 2.20
GHF0503 RC 67 17/02/2022 199909.544 7577849.346 426.398 329 -90 M1 40.5 43.5 3 1.91
GHF0503 RC 67 17/02/2022 199909.544 7577849.346 426.398 329 -90 M2 57 60 3 13.16
GHF0504 RC 66.5 17/02/2022 199895.707 7577849.66 425.105 359 -89 M1 40.5 43.5 3 2.29
GHF0504 RC 66.5 17/02/2022 199895.707 7577849.66 425.105 359 -89 M2 55 60 5 2.83
GHF0505 RC 66.5 17/02/2022 199902.69 7577842.75 425.75 8 -89 M1 39.5 43 3.5 2.05
GHF0505 RC 66.5 17/02/2022 199902.69 7577842.75 425.75 8 -89 M2 55 59.5 4.5 4.68
GHF0506 RC 64 17/02/2022 199909.862 7577835.49 424.694 126 -89 M1 38 39.5 1.5 18.94
GHF0506 RC 64 17/02/2022 199909.862 7577835.49 424.694 126 -89 M2 51 57 6 2.07
GHF0507 RC 66 17/02/2022 199895.904 7577835.641 425.245 21 -90 M1 39 41.5 2.5 8.14
GHF0507 RC 66 17/02/2022 199895.904 7577835.641 425.245 21 -90 M2 53.5 57.5 4 2.52
GHF0508 RC 66 17/02/2022 199874.408 7577842.822 422.616 335 -90 M1 39.5 42.5 3 4.03
GHF0508 RC 66 17/02/2022 199874.408 7577842.822 422.616 335 -90 M2 54.5 58 3.5 1.73

GHF0509 RC 66.5 17/02/2022 199881.59 7577835.773 424.447 271 -89 M1 40 40.5 0.5 7.31
GHF0509 RC 66.5 17/02/2022 199881.59 7577835.773 424.447 271 -89 M2 54.5 58 3.5 4.40
GHF0510 RC 65.5 17/02/2022 199888.474 7577828.424 425.138 357 -89 M1 39.5 41 1.5 1.25
GHF0510 RC 65.5 17/02/2022 199888.474 7577828.424 425.138 357 -89 M2 54.5 57.5 3 0.89
GHF0511 RC 63.5 17/02/2022 199895.712 7577821.243 424.311 338 -89 M1 36 39.5 3.5 4.41
GHF0511 RC 63.5 17/02/2022 199895.712 7577821.243 424.311 338 -89 M2 50.5 55.5 5 4.81
GHF0512 RC 67 17/02/2022 199867.489 7577835.645 423.286 339 -90 M1 40 42.5 2.5 2.52
GHF0512 RC 67 17/02/2022 199867.489 7577835.645 423.286 339 -90 M2 54 58.5 4.5 1.69
GHF0513 RC 65.5 17/02/2022 199881.505 7577821.485 425.682 22 -90 M1 38.5 41.5 3 0.63
GHF0513 RC 65.5 17/02/2022 199881.505 7577821.485 425.682 22 -90 M2 55 57 2 1.14
GHF0514 RC 69 17/02/2022 199860.448 7577828.847 425.482 324 -89 M1 43.5 45 1.5 4.88
GHF0514 RC 69 17/02/2022 199860.448 7577828.847 425.482 324 -89 M2 57 60 3 1.69
GHF0515 RC 67.5 17/02/2022 199867.507 7577821.505 426.395 0 -90 M1 42.5 45 2.5 6.63
GHF0515 RC 67.5 17/02/2022 199867.507 7577821.505 426.395 0 -90 M2 56 59.5 3.5 1.70
GHF0516 RC 65.5 17/02/2022 199874.468 7577814.464 426.452 25 -89 M1 40.5 43.5 3 4.71
GHF0517 RC 63.5 17/02/2022 199881.814 7577807.046 425.239 8 -90 M1 37.5 41 3.5 5.04
GHF0517 RC 63.5 17/02/2022 199881.814 7577807.046 425.239 8 -90 M2 51 56 5 1.50
GHF0518 RC 70.5 17/02/2022 199853.458 7577821.26 426.932 221 -90 M1 45.5 46.5 1 30.39
GHF0518 RC 70.5 17/02/2022 199853.458 7577821.26 426.932 221 -90 M2 59 61.5 2.5 0.96
GHF0519 RC 66 17/02/2022 199867.398 7577807.3 427.054 59 -90 M1 43 44.5 1.5 3.13
GHF0519 RC 66 17/02/2022 199867.398 7577807.3 427.054 59 -90 M2 55 58.5 3.5 2.52
GHF0520 RC 69.5 17/02/2022 199853.327 7577807.42 428.033 327 -89 M1 47 50 3 1.50
GHF0520 RC 69.5 17/02/2022 199853.327 7577807.42 428.033 327 -89 M2 57.5 61.5 4 2.74
GHF0521 RC 67 18/02/2022 199860.42 7577800.148 427.581 350 -90 M1 45.5 47 1.5 5.17
GHF0521 RC 67 18/02/2022 199860.42 7577800.148 427.581 350 -90 M2 58 60 2 1.14
GHF0522 RC 75 18/02/2022 199853.436 7577793.183 428.089 6 -90 M1 46 47.5 1.5 23.35
GHF0522 RC 75 18/02/2022 199853.436 7577793.183 428.089 6 -90 M2 57 60 3 3.86
GHF0523 RC 70 18/02/2022 199839.262 7577793.253 428.588 3 -89 M1 47.5 52 4.5 15.23
GHF0523 RC 70 18/02/2022 199839.262 7577793.253 428.588 3 -89 M2 59 62.5 3.5 3.05
GHF0524 RC 69 18/02/2022 199845.971 7577786.109 428.521 4 -89 M2 57.5 62 4.5 3.86
GHF0525 RC 69.5 18/02/2022 199839.371 7577779.114 428.726 297 -89 M1 47 49.5 2.5 13.54
GHF0525 RC 69.5 18/02/2022 199839.371 7577779.114 428.726 297 -89 M2 61 62 1 14.15
GHF0526 RC 70.5 18/02/2022 199824.966 7577778.923 428.566 0 -90 M1 47 50.5 3.5 43.62
GHF0526 RC 70.5 18/02/2022 199824.966 7577778.923 428.566 0 -90 M2 59 60 1 6.43
GHF0527 RC 69.5 18/02/2022 199832.043 7577772.049 428.968 355 -90 M1 46.5 48.5 2 4.31
GHF0527 RC 69.5 18/02/2022 199832.043 7577772.049 428.968 355 -90 M2 58.5 61.5 3 4.12
GHF0528 RC 70 18/02/2022 199825.034 7577765.176 429.205 10 -89 M1 46.5 47.5 1 5.29
GHF0528 RC 70 18/02/2022 199825.034 7577765.176 429.205 10 -89 M2 59 62 3 4.72
GHF0529 RC 72 9/02/2022 199811.575 7577763.987 428.955 0 -90 M1 47.5 50 2.5 2.03
GHF0529 RC 72 9/02/2022 199811.575 7577763.987 428.955 0 -90 M2 60 61 1 2.24
GHF0530 RC 71 18/02/2022 199817.933 7577758.094 429.752 0 -90 M1 47 49.5 2.5 1.40
GHF0530 RC 71 18/02/2022 199817.933 7577758.094 429.752 0 -90 M2 59.5 61.5 2 1.89
GHF0531 RC 68.5 18/02/2022 199825.226 7577750.574 428.659 348 -89 M1 45 46 1 12.26
GHF0531 RC 68.5 18/02/2022 199825.226 7577750.574 428.659 348 -89 M2 57 59 2 2.34
GHF0532 RC 66.5 18/02/2022 199831.972 7577743.755 428.093 0 -90 M1 42.5 44.5 2 3.36
GHF0532 RC 66.5 18/02/2022 199831.972 7577743.755 428.093 0 -90 M2 55 57 2 3.34
GHF0533 RC 72 11/02/2022 199810.891 7577750.922 430.132 7 -89 M1 48 48.5 0.5 1.71
GHF0533 RC 72 11/02/2022 199810.891 7577750.922 430.132 7 -89 M2 60 62 2 2.37
GHF0534 RC 67.5 18/02/2022 199824.948 7577736.639 428.67 1 -90 M1 44 44.5 0.5 3.42
GHF0534 RC 67.5 18/02/2022 199824.948 7577736.639 428.67 1 -90 M2 55.5 57 1.5 0.78
GHF0535 RC 72.5 11/02/2022 199796.831 7577750.578 429.405 0 -90 M2 61 63 2 2.45
GHF0536 RC 72.5 11/02/2022 199803.83 7577743.566 430.642 12 -89 M1 48 48.5 0.5 0.94
GHF0536 RC 72.5 11/02/2022 199803.83 7577743.566 430.642 12 -89 M2 59.5 60.5 1 3.74
GHF0537 RC 71 11/02/2022 199811.166 7577736.723 430.42 168 -89 M1 46.5 47 0.5 0.80
GHF0537 RC 71 11/02/2022 199811.166 7577736.723 430.42 168 -89 M2 60 60.5 0.5 0.54
GHF0538 RC 73 11/02/2022 199796.777 7577736.718 430.893 357 -89 M1 47 48 1 4.59
GHF0540 RC 73.5 11/02/2022 199789.838 7577729.739 431.062 341 -89 M1 47.5 49 1.5 2.32
GHF0540 RC 73.5 11/02/2022 199789.838 7577729.739 431.062 341 -89 M2 61 63.5 2.5 0.70
GHF0541 RC 70.5 11/02/2022 199799.851 7577721.897 429.287 0 -90 M1 44.5 45.5 1 5.70
GHF0541 RC 70.5 11/02/2022 199799.851 7577721.897 429.287 0 -90 M2 59.5 62 2.5 0.61
GHF0542 RC 73 11/02/2022 199782.583 7577722.526 430.745 348 -90 M2 60 63.5 3.5 1.00
GHF0543 RC 75 12/02/2022 199768.774 7577722.593 431.139 0 -90 M2 63 66 3 1.25
GHF0544 RC 73 11/02/2022 199775.636 7577715.626 430.899 8 -89 M1 48 49 1 1.57
GHF0544 RC 73 11/02/2022 199775.636 7577715.626 430.899 8 -89 M2 60.5 63.5 3 2.99
GHF0545 RC 70 11/02/2022 199782.425 7577708.503 429.249 0 -90 M1 48 52 4 3.80
GHF0545 RC 70 11/02/2022 199782.425 7577708.503 429.249 0 -90 M2 55 57.5 2.5 1.02
GHF0546 RC 73.5 14/02/2022 199754.583 7577722.372 428.367 0 -90 M1 48.5 49 0.5 3.95

GHF0547 RC 73 15/02/2022 199768.325 7577708.363 430.775 336 -89 M1 51 52.5 1.5 1.28
 GHF0547 RC 73 15/02/2022 199768.325 7577708.363 430.775 336 -89 M2 61.5 65.5 4 1.34
 GHF0548 RC 73 7/02/2022 199748.158 7577715.796 427.932 1 -90 M2 61.5 63 1.5 2.36
 GHF0549 RC 74 14/02/2022 199754.274 7577708.261 430.144 0 -90 M1 49 50 1 8.94
 GHF0549 RC 74 14/02/2022 199754.274 7577708.261 430.144 0 -90 M2 62.5 63.5 1 3.51
 GHF0550 RC 72.5 15/02/2022 199761.414 7577701.435 430.521 87 -89 M1 50 51.5 1.5 1.47
 GHF0550 RC 72.5 15/02/2022 199761.414 7577701.435 430.521 87 -89 M2 62 62.5 0.5 3.62
 GHF0551 RC 68.5 9/02/2022 199768.32 7577694.14 428.958 0 -90 M1 48.5 49 0.5 2.02
 GHF0551 RC 68.5 9/02/2022 199768.32 7577694.14 428.958 0 -90 M2 58 61 3 3.90
 GHF0552 RC 72.5 6/02/2022 199740.325 7577708.476 427.375 0 -90 M1 47.5 48.5 1 6.98
 GHF0552 RC 72.5 6/02/2022 199740.325 7577708.476 427.375 0 -90 M2 61.5 64.5 3 3.77
 GHF0553 RC 71.5 18/02/2022 199754.258 7577694.222 429.892 0 -90 M1 46.5 48.5 2 4.59
 GHF0553 RC 71.5 18/02/2022 199754.258 7577694.222 429.892 0 -90 M2 60 63.5 3.5 2.69
 GHF0554 RC 72 5/02/2022 199733.079 7577701.309 427.119 0 -90 M1 47.5 48 0.5 3.44
 GHF0554 RC 72 5/02/2022 199733.079 7577701.309 427.119 0 -90 M2 61.5 64.5 3 15.30
 GHF0555 RC 72.5 8/02/2022 199741.293 7577694.98 428.848 0 -90 M1 47.5 48.5 1 3.60
 GHF0556 RC 54 6/02/2022 199747.106 7577687.232 428.884 1 -90 M1 49 49.5 0.5 0.58
 GHF0556 RC 54 6/02/2022 199747.106 7577687.232 428.884 1 -90 M2 60 62.5 2.5 1.11
 GHF0557 RC 66.5 5/02/2022 199753.952 7577681.506 427.433 0 -90 M1 45.5 46 0.5 0.65
 GHF0557 RC 66.5 5/02/2022 199753.952 7577681.506 427.433 0 -90 M2 58.5 60.5 2 1.64
 GHF0558 RC 72 4/02/2022 199725.986 7577694.201 426.777 0 -90 M1 51 51.5 0.5 4.29
 GHF0558 RC 72 4/02/2022 199725.986 7577694.201 426.777 0 -90 M2 63 64.5 1.5 3.66
 GHF0559 RC 69 4/02/2022 199739.87 7577679.766 427.234 0 -90 M2 60.5 61.5 1 0.93
 GHF0560 RC 72 3/02/2022 199717.282 7577687.007 426.274 0 -90 M1 50.5 52 1.5 7.16
 GHF0560 RC 72 3/02/2022 199717.282 7577687.007 426.274 0 -90 M2 62.5 64.5 2 1.91
 GHF0561 RC 70 3/02/2022 199725.817 7577680.157 426.56 0 -90 M1 49.5 50.5 1 8.17
 GHF0561 RC 70 3/02/2022 199725.817 7577680.157 426.56 0 -90 M2 61.5 63.5 2 1.24
 GHF0562 RC 66.5 4/02/2022 199733.444 7577674.908 425.402 0 -90 M1 42.5 44.5 2 16.36
 GHF0562 RC 66.5 4/02/2022 199733.444 7577674.908 425.402 0 -90 M2 60 62 2 1.25

1 Refer to the Company's news releases dated June 14, 2022.

2 Refer to the Company's news releases dated December 13, 2021 and May 24, 2022.

3 Refer to the Company's news release dated April 30, 2021 and the report titled "Preliminary Economic Assessment on the Beatons Creek Gold Project, Western Australia" (the "PEA") with an effective date of February 5, 2021 and an issue date of April 30, 2021. The mineral resource estimate in the PEA has not been adjusted for depletion. Mineral resources that are not mineral reserves do not have demonstrated economic viability.

4 Refer to the Company's news releases dated October 12, 2021 and April 7, 2022.

5 Refer to the Company's news release dated October 12, 2021.

Dieser Artikel stammt von [Rohstoff-Welt.de](https://www.rohstoff-welt.de)

Die URL für diesen Artikel lautet:

<https://www.rohstoff-welt.de/news/413950--Novo-Resources-Corp.-Beatons-Creek-Fresh-Feasibility-Study-Update.html>

Für den Inhalt des Beitrages ist allein der Autor verantwortlich bzw. die aufgeführte Quelle. Bild- oder Filmrechte liegen beim Autor/Quelle bzw. bei der vom ihm benannten Quelle. Bei Übersetzungen können Fehler nicht ausgeschlossen werden. Der vertretene Standpunkt eines Autors spiegelt generell nicht die Meinung des Webseiten-Betreibers wieder. Mittels der Veröffentlichung will dieser lediglich ein pluralistisches Meinungsbild darstellen. Direkte oder indirekte Aussagen in einem Beitrag stellen keinerlei Aufforderung zum Kauf-/Verkauf von Wertpapieren dar. Wir wehren uns gegen jede Form von Hass, Diskriminierung und Verletzung der Menschenwürde. Beachten Sie bitte auch unsere [AGB/Disclaimer!](#)

Die Reproduktion, Modifikation oder Verwendung der Inhalte ganz oder teilweise ohne schriftliche Genehmigung ist untersagt!
 Alle Angaben ohne Gewähr! Copyright © by Rohstoff-Welt.de -1999-2026. Es gelten unsere [AGB](#) und [Datenschutzrichtlinien](#).